

TCD

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

The effect of changing sea ice on the vulnerability of Arctic coasts

K. R. Barnhart^{1,2}, I. Overeem², and R. S. Anderson^{1,2}

¹Department of Geological Sciences, University of Colorado at Boulder, Boulder, CO, USA

²Institute of Arctic and Alpine Research, University of Colorado at Boulder, Boulder, CO, USA

Received: 14 April 2014 – Accepted: 18 April 2014 – Published: 7 May 2014

Correspondence to: K. R. Barnhart (katherine.barnhart@colorado.edu)

Published by Copernicus Publications on behalf of the European Geosciences Union.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Abstract

Shorefast sea ice prevents the interaction of the land and the ocean in the Arctic winter and influences this interaction in the summer by governing the fetch. In many parts of the Arctic the sea-ice-free season is increasing in duration, and the summertime sea ice extents are decreasing. Sea ice provides a first order control on the vulnerability of Arctic coasts to erosion, inundation, and damage to settlements and infrastructure. We ask how the changing sea ice cover has influenced coastal erosion over the satellite record. First, we present a pan-Arctic analysis of satellite-based sea ice concentration specifically along the Arctic coasts. The median length of the 2012 open water season in comparison to 1979 expanded by between 1.5 and 3-fold by Arctic sea sector which allows for open water during the stormy Arctic fall. Second, we present a case study of Drew Point, Alaska, a site on the Beaufort Sea characterized by ice-rich permafrost and rapid coastal erosion rates where both the duration of the sea ice free season and distance to the sea ice edge, particularly towards the northwest, has increased. At Drew Point, winds from the northwest result in increased water levels at the coast and control the process of submarine notch incision, the rate-limiting step of coastal retreat. When open water conditions exist, the distance to the sea ice edge exerts control on the water level and wave field through its control on fetch. We find that the extreme values of water level set-up have increased, consistent with increasing fetch.

1 Introduction

Arctic coasts are at the mercy of sea ice: the processes of erosion and sedimentation are thresholded by the presence or absence of nearshore sea ice. Shore-fast sea ice prevents erosion, suspension, and transport of sediment by wave action in the nearshore water. In regions dominated by ice-rich permafrost, erosion of the coastline is controlled by the delivery of heat to the coast, which is also influenced by sea ice cover. Sea ice does not exclusively prevent erosion; land-fast sea ice in shallow

TCD

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

water can incorporate sediment and carry it away as sea ice drifts (Eicken et al., 2005), ice pile-up and ride-up can transport sediment (Kovacs and Sodhi, 1980), and ice keels can resuspend and transport shelf sediment (Rearic et al., 1990; Héquette et al., 1995). But the rates of these sediment transport processes are smaller than those driven by the nearshore ocean. The sea ice is thus the first-order link between Arctic coasts and the nearshore environment.

The Arctic environment is changing, and this has resulted in thinner sea ice and more extensive summertime open water IPCC (2013). We ask how the changing sea ice characteristics have manifested at the coast.

We consider vulnerability as the inability of a system to resist change. In the context of Arctic coasts, vulnerability results from the interplay between resisting and forcing factors, such as strength of the terrestrial substrate (resisting) and the passage of storms during times of open water (forcing). We can also cast this dichotomy in terms of static and dynamic factors: the lithology and geomorphology of the coastline are static, while the length of the sea-ice-free season, the distance to the sea ice edge, the magnitude and frequency of storms, and the water temperature are all dynamic.

Coastal erosion or deposition results from the convolution of the nearshore water and sea ice dynamics, the nature of the terrestrial substrate, and geomorphic processes that govern material removal and distribution. Ultimately the nearshore wave field and water level provides the energy to do work on the landscape. Depending on the geomorphology of a coastline, the wave field or water level may be more important in governing its vulnerability. For example, low-lying areas subject to inundation may be most impacted by water level set up associated with large storm surges, whereas sandy beaches and barrier islands will be influenced by changes in the wave field. Along ice-rich permafrost coastal bluffs, the length of time that the nearshore water is set up to the base of the bluff is most significant (Barnhart et al., 2014). In other environments, like the large Arctic deltas, the processes of erosion are different, but exposure to some combination of the water level and wave field is likely important. With the exception of

damage by sea ice shove, the processes described are prevented by the sheath of land-fast sea ice cover in the winter.

The changes in the duration of Arctic sea ice cover exert a first order control on the vulnerability of the Arctic coastline. We show that when open water is present, the sea ice still exerts influence by controlling (1) the fetch, or the distance over which wind can interact with the nearshore water creating storms surge and waves, and (2) the area over which the ocean can absorb incident solar radiation. The combination of environmental change in the Arctic and the importance of sea ice in thresholding geomorphic processes motivates a process-based understanding of the links between sea ice and coastal processes. Here, we focus on the impact of changing sea ice, particularly the increased fetch, on the nearshore water conditions.

We use satellite-based observations of sea ice to construct a whole-Arctic analysis of the changing open water season along the Arctic coastline. We then combine this analysis with observations of the local wind field and the nearshore water level and wave field to examine the changing environment at one site – Drew Point, Alaska, through the lens of the changing sea ice season. The Drew Point area is characterized by exposed ice-rich permafrost bluffs that erode rapidly when water is set up above the base of the bluffs. It has experienced both changes in the sea-ice-free season and an increase in coastal erosion rates. Our goal is to understand the extent to which changes in sea ice cover and the nearshore conditions relate to coastal erosion. We use a numerical model for nearshore storm surge and the wave field to reconstruct storm surge and waves for the period 1979–2012 and to explore the sensitivity of the nearshore conditions to changing fetch. We then analyze the 1979–2012 hindcast of environmental conditions to identify how the changes in the sea ice cover manifest in the nearshore conditions.

TCD

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

⏪

⏩

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



2 Arctic climate and Arctic coasts

The Arctic environment is warming (Comiso, 2003; Blunden and Arndt, 2012). The frequency and intensity of storms are anticipated to increase, particularly in the autumn and winter (ACIA, 2004; Manson and Solomon, 2007; Clow et al., 2011). Observed Arctic storminess is characterized by large inter-annual variability and no long-term trends are detectable in wind records from 1950–2000 (Atkinson, 2005). However, an analysis of the NCEP/NCAR reanalysis by Sepp and Jaagus (2011) found that the number of cyclones that entered the Arctic basin had increased significantly ($p < 0.05$ over the period 1948–2002) while no significant trends were found in the number of cyclones that had formed within the Arctic.

In conjunction with decreased sea ice extent (Serreze et al., 2007), decreasing sea ice thickness and age (Maslanik et al., 2007, 2011), and increased duration of the sea-ice-free season (Stammerjohn et al., 2012), the changes in storminess have the potential to result in increased storm surge and wave action and increasing the vulnerability of Arctic coasts to geomorphic change, inundation, and damage to infrastructure. These environmental changes impact not only the duration of time over which the ocean and land can interact, but also the aerial extent of open water which provides greater fetch and associated increased surge and wave climate (Lintern et al., 2011; Overeem et al., 2011).

The average rate of coastal erosion for the portion of the Arctic coast considered in the Arctic Coastal Dynamics Database is 0.5 myr^{-1} (Lantuit et al., 2012). This project analyzed $\sim 25\%$ of the Northern Hemisphere permafrost impacted coastline and found coastal erosion rates that reach 8.4 myr^{-1} ; 89% of the segments have erosion rates below 2 myr^{-1} . The highest rates of Arctic coastal erosion occur in ice-rich permafrost bluffs which only occur along cold coasts. Elsewhere in the world, some of the most extreme rates of coastal erosion occur on sandy coasts; for example erosion rates in Mississippi, Texas, Louisiana reach up to 12 myr^{-1} (Morton et al., 2005), and most of the globe's sandy coastlines have retreated since 1900 (Bird, 1985).

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



A comparison of erosion rates along sandy coasts and ice-rich permafrost blocks is not that meaningful. There is no good analogy for permafrost bluffs outside of the Arctic – they are highly competent when frozen, and in that regard are similar to rocky coastlines. However, unlike rocky coastlines, permafrost bluffs can thaw and thereby rapidly lose all competence. Rocky coastline erode at rates of order 10 cm yr^{-1} (e.g. Moore and Griggs, 2002, measured over 41 years) while cliffs in softer material erode at up to 4.5 myr^{-1} (e.g. Brooks and Spencer, 2010, measured over 125 years), both erode much more slowly than permafrost bluffs.

3 Overview of the Drew Point coast

Drew Point is located along the most rapidly eroding segment of the central-western Alaskan Beaufort Sea coast. At Drew Point, the length of the sea-ice-free season over the satellite record has expanded at a rate of 1.75 day yr^{-1} (over the period 1979–2009, Overeem et al., 2011, also Fig. 1). The duration of the sea-ice-free season over this time period has doubled from ~ 45 days of open water per year to ~ 95 days (Overeem et al., 2011). Open water conditions currently begin in mid-July to early-August and end in late-September to early-October. The duration of sea-ice-free conditions for the period 1979–2009 expanded faster into the autumn than into the spring (Overeem et al., 2011, also Fig. 2). Autumn is typically stormier than summer in the Beaufort Sea region. Over the period 1950–2000, an average of 8.5 storms (wind speeds greater than 10 ms^{-1} for a duration of 48 h) occurred in September and October combined, whereas an average of 6.5 storms occurred in July and August (Atkinson, 2005).

To the north of Drew Point, the Beaufort Shelf slopes north at $\sim 0.001 \text{ m m}^{-1}$ (Ricketts, 1953; Greenberg et al., 1981) and is roughly uniform along the coastline. The mean tidal range at the nearest NOAA tide gauge station (Prudhoe Bay 240 km to the WSW) is 15 cm for daily to monthly cycles which are superimposed on a yearly tidal cycle with a range of 66 cm with a peak in late July [NOAA Tide Gauge Station 9497645]. The local wind field is dominated by winds from the east and northeast with a smaller

secondary maximum from the west (Urban and Clow, 2013, and Fig. 3a and b). When surface winds are from the west, water is pushed towards the shore by Ekman transport (Fig. 4). Winds from the east set down water levels. These observations are consistent with bathystrophic surge theory (e.g., Dean and Dalrymple, 1991). Winds from the west are typically associated with the passage of synoptic-scale storms. In the spring and autumn, the easterly winds are consistent with winds coming off the Beaufort Sea High, a persistent atmospheric feature characterized by high sea level air pressure (Serreze and Barrett, 2011).

Acceleration of coastal retreat at Drew Point and along the 70 km coastline to the west has accompanied the change in the length of the sea-ice-free season. The rate of area loss more than doubled from $0.48 \text{ km}^2 \text{ yr}^{-1}$ for 1955–1985 to $1.08 \text{ km}^2 \text{ yr}^{-1}$ for 1985–2005 (Mars and Houseknecht, 2009). Jones et al. (2009) found that coastal erosion rates increased from 6.8 myr^{-1} for 1955–1979 to 8.7 myr^{-1} for 1979–2002 and 13.6 myr^{-1} for 2002–2007. Barnhart et al. (2014) report that the mean erosion rate over a 7 km stretch of the central-west Beaufort Sea coast just east of Drew Point was 15 myr^{-1} (2008–2011) and 19 myr^{-1} (2011–2012). Early work in the region documented coastal retreat rates that locally reached 18 myr^{-1} (during the period 1950–1980) (Reimnitz et al., 1985, 1988). More recently Wobus et al. (2011) reported local rates that reached 30 myr^{-1} in the summer of 2008.

At Drew Point the process of erosion is dramatic. Four meter high bluffs stand between the low relief coastal plain and the Beaufort Sea. The bluffs are composed of ice-rich permafrost (50 to 80 % by mass), organic material, and silt and clay-sized inorganic material (Wobus et al., 2011). The permafrost depth extends to 320 m into the subsurface (<http://www.gtnp.org/>), the active layer is 30–50 cm deep, and the mean annual surface temperature ranges from -8.5 to -6.5°C (1998–2011 Urban and Clow, 2014). The ground is dissected by massive-ice wedges that extend around 4 m into the subsurface. The bluffs erode through the process of failure on an ice wedge after a notch is carved at the base of the coastal bluff by submarine erosion (Kobayashi, 1985; Kobayashi et al., 1999; Hoque and Pollard, 2009; Wobus et al., 2011; Barnhart

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



et al., 2014). This failure creates a toppled block that subsequently rotates towards the sea as it degrades by melting of interstitial ice. The process of coastal erosion in this area is most sensitive to water levels that are set up above the base of the bluffs (Barnhart et al., 2014).

4 Data

Our analysis is based on three publicly available datasets: pan-Arctic sea ice concentrations and meteorology from Drew Point and Barrow, Alaska; and local field observations of the water level and wave field collected in the summers of 2009 and 2010 at Drew Point.

Arctic-wide sea ice: the concentration of sea ice is given by the Nimbus7 SMMR/SSM/I and DMSP SSMI Passive Microwave Sea Ice Concentrations (referred to hereafter as sea ice concentration or SIC) derived from brightness temperature (Cavaliere et al., 1996). This dataset is available from the National Snow and Ice Data Center (NSIDC, <http://nsidc.org/data/nsidc-0051.html>), and is used to determine open water conditions and locate the sea ice edge.

Drew Point wind speed and direction: wind speed and direction have been observed by the USGS at Drew Point since 7 August 2004 (Urban and Clow, 2013). On 29 June 2008, a second station was installed closer to the coast (<http://data.usgs.gov/climateMonitoring/station/show/5>, called CU Drew Point Site). Both stations are Campbell Scientific meteorological stations that measured wind speed and direction every 30 s, recording an average value once per hour.

Barrow wind speed and direction: the hourly wind speed and direction measured at Barrow (<http://www.esrl.noaa.gov/gmd/obop/brw/>) are used to calculate wind setup and wave field. Wind speed and direction measured at Barrow are adjusted using the transfer function developed by Overeem et al. (2011) to relate the wind field at Barrow to that at Drew Point. This transfer function was optimized for winds greater than 5 ms^{-1} during sea-ice-free conditions, and is based on comparison of wind speed

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



and direction measured at Barrow with those measured at the CU Drew Point station over the time period June 2008–September 2010 ($R^2 = 0.8$). We also examined the wind record collected by NOAA at Prudhoe Bay (NOAA station #9497645) and found that the wind records at Barrow, Drew Point, and Prudhoe Bay were all visually similar.

5 *Drew Point water level and wave field*: the water level, significant wave height, and wave period were measured with wave field loggers custom built by Tim Stanton at the Naval Postgraduate School. Four wave loggers were deployed in 2009 in depths ranging from 1.9 to 6.8 m (up to 9 km from the shore). One wave logger was deployed
10 in 2010 at a water depth of 88 cm. These observations are summarized by Barnhart et al. (2014).

5 Changes in the sea-ice-free season at the coast

We present three novel analyses to illustrate how the sea-ice-free season has changed along the Arctic coastline. We calculate the change in the number of open water days at each coastal cell over the satellite record and document how open water has expanded into the early summer and fall. We document how fetch over the length of the open water season has changed at Drew Point and examine how this is related to the duration of the sea-ice-free season. Finally we employ a storm surge and wave model
15 to reconstruct the nearshore conditions at Drew Point for the period 1979–2012 and use the modeled water level and wave height histories to produce quantitative metrics
20 for the water exposure of the coastal bluffs at Drew Point.

5.1 Whole Arctic analysis

The duration of the sea-ice-free season controls the length of time that open water can interact with the coast to accomplish geomorphic work. We calculate the number of sea-ice-free days at each nearshore cell for the period 1979–2012. Open water
25 is defined as sea ice concentrations less than 15%, a standard threshold for identifying

TCO

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



trend (Fig. 1b). The difference between Beaufort and East Siberian Sea regions and the Canadian Arctic Archipelago pattern is controlled by the large scale patterns of sea ice drift which move sea ice clockwise around the Beaufort Gyre and from the Siberian and Alaskan coast toward the Transpolar Drift Current and out Fram Strait (Jones, 2001; Serreze and Barry, 2005). Smaller surface currents move sea ice from the Barents Sea into the Transpolar Drift Current (Jones, 2001; Serreze and Barry, 2005).

We also determine trends in the first and last day of continuous open water (Fig. 2). The open water season is expanding asymmetrically, with faster rates of expansion into the fall than the spring. This is significant for coastal vulnerability because of variability in the storm climate in the spring and the fall (Atkinson, 2005). Expansion into the mid-summer provides open water at times of higher insolation. This results in higher water temperatures which impact coastal erosion rates in regions with high ice content.

5.1.1 Spatial patterns of sea ice change, coastal erosion, and ice content

While we cannot address the details of the changing nearshore environment, or even the directional fetch, across the whole Arctic, we can consider the changing length of open water days (Fig. 1) in the context of some of the other key factors that govern vulnerability. We present whole-Arctic maps of coastal erosion rate, backshore elevation, and ground ice content compiled as part of the Arctic Coastal Dynamics project (Fig. 5) (Lantuit et al., 2012). Particularly rapid erosion ($> 2 \text{ myr}^{-1}$) occurs in the Beaufort, East Siberian, and Beaufort sea regions. Lantuit et al. (2012) found that coastal erosion rates are higher on unlithified coastal segments, that erosion rates correlated positively but weakly with ground ice content, and even more weakly with backshore elevation.

We compare coastal erosion rates and ice content from Lantuit et al. (2012) for coastal database segments with erosion rates greater than 0.1 myr^{-1} with the 2012 number of sea-ice-free days (Fig. 6). The relationship between the duration of open water, the erosion rate, and ice content is not simple. It appears that up to ~ 220 open

water days, the longer the sea-ice-free season and the higher the ice content, the greater the capacity for high coastal erosion rates. Still, coastal segments with short open water seasons and high erosion rates, and segments with high ice content, long open water seasons, and low erosion rates exist. Figure 6 appears to highlight the thresholded behavior of coastal vulnerability; rapid erosion along segments with high ice content and long open water seasons will only occur if a storm passes.

5.1.2 Well studied Arctic coasts

Before focusing on Drew Point, Alaska (Sect. 3) we discuss the whole-Arctic results in the context of the other well studied coastlines in Russia, the Canadian Beaufort Sea, the Canadian Arctic Archipelago, and Svalbard. Multi-temporal studies are required to identify changes in coastal processes and evaluate connections with forcing changes, yet very few areas have multi-temporal observations (Lantuit et al., 2013). We expect to see a relationship between sea ice change and coastal erosion rate in places with high erosion rates and places with large increases in the length of the sea-ice-free season.

Multi-temporal observations between 1984–2002 are available at Marre-Sale, a site along the Kara Sea with 10–30 m high coastal bluffs with ice content of between 20–60% (Vasiliev et al., 2005). At this site, erosion occurs by thermal erosion at the base of the cliff (Vasiliev et al., 2005) and the number of sea-ice-free days per year has increased by between 1.5–3 day yr^{-1} . Erosion rates are best correlated with total wave energy which has not increased through time but instead shows a maximum in the late 1980s (Vasiliev et al., 2005).

At the Bykovsky Peninsula on the Laptev Sea, a site with high ice content characterized by either coastal cliffs or low-lying thermokarst depressions where we find the number of sea-ice-free days has increased at 0.5–1 day yr^{-1} , coastal erosion rates measured between 1951–2006 show no trend in time or relation to storm records (Lantuit et al., 2012). Coastal erosion rates along the Bykovsky Peninsula coastline is strongly affected by the lithology and geomorphology with the highest coastal erosion

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



rates occurring in depressions created by the thawing of ice-rich permafrost and the lowest rates occurring along sand bars (Lantuit et al., 2012).

Further east on the Laptev Sea, three sites with high ice content show increases in mean annual erosion rates and spatial variability associated with lithology and geomorphology (measured between 1965–2011) (Günther et al., 2013). In this area there are fewer coastal cells with significant trends over the 1979–2012 time period, but those that are significant give trends of $0.5\text{--}1\text{ day yr}^{-1}$. We know of no multi-temporal coastal erosion studies further to the east along the portion of the East Siberian Sea coast with rapid sea ice change.

The erosion of the low bluffs at Elson Lagoon, Barrow, Alaska, increased from 0.56 myr^{-1} (1948–1979) to 0.86 myr^{-1} (1979–2000) Brown et al. (2003). Since 1979 we find that the length of the sea ice free season has increased by 2 day yr^{-1} at Barrow and by up to 3.4 day yr^{-1} just to the west. Further to the east, along the Beaufort Lagoon the length of the sea ice free season has increased $1.5\text{--}2\text{ day yr}^{-1}$ and coastal erosion was constant at 0.5 myr^{-1} over two time periods (1948–1978, 1978–2001) with substantial variability due to permafrost characteristics (Jorgenson et al., 2002).

At Herschel Island just to the west of the Mackenzie Delta, we find that the sea-ice-free season has increased by $1\text{--}1.5\text{ day yr}^{-1}$ and Lantuit and Pollard (2008) found the mean coastal retreat rate decreased over the period 1954–2000. The regions of Herschel Island with the highest erosion rates are northwest facing and are exposed to the wind (Lantuit and Pollard, 2008). While the mean rate of coastal erosion declined, the regions of Herschel Island with the highest ice content show an increase in thaw slump activity and an increase in the coastal retreat rate (Lantuit and Pollard, 2008).

Along the Canada Beaufort sea in the Mackenzie Delta region the sea-ice-free season has expanded around 1 day yr^{-1} . Mackenzie river discharge has increased over 1977–2007, with early season discharge increasing and peak month discharge decreasing (Overeem and Syvitski, 2010). Similar to Herschel Island to the west, in this region the coastal dynamics are characterized by retreat of the shoreline but do not show an increase in rates through time (measurements made between 1972–2000

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[⏪](#)[⏩](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

Solomon, 2005). The highest rates are along coastlines exposed to winds from the northwest which set water up and the lowest rates are in areas sheltered from the wind (Solomon, 2005). There is significant spatial variability within and between coastal zones, associated with variations in geomorphology and lithology (Solomon, 2005).

5 In the Canadian Arctic Archipelago, the coasts are rocky and the sea ice cover change is variable. At Resolute Bay, a gravel beach, progradation dominated over erosion over the period 1958–2006 due to a combination of post-glacial rebound related emergence and sediment supply (St-Hilaire-Gravel et al., 2012). In the northern portion of the Canadian Arctic Archipelago, the sea-ice-free season has not changed, but in
10 Resolute Bay it has increased by just under 1 day yr⁻¹. In this region, further increases in the duration of sea-ice-free conditions is will likely not result in rapid increases in erosion due to the resistant nature of the terrestrial lithology. Emergence also serves to create land.

In Svalbard there is little ice rich permafrost and sea ice change is spatially variable.
15 Along the northern portion of the archipelago the sea-ice-free season has expanded by up to 3.3 day yr⁻¹ while rates of expansion are lower in the southeast and are not significant in the southwest. Three sites in unconsolidated sediments in central Spitsbergen near Longyearbyen give low erosion rates (< 1 myr⁻¹) and have decelerated over the period 1977–2003 associated with the progradation of a delta (Sessford, 2013). Sites
20 further south, near Recherchefjorden, show net erosion but no clear temporal trends (Zagórski, 2011).

These studies highlight the complicated relationship between changes in the sea ice season and changes in coastal erosion rates. The length of the sea-ice-free season has increased along all of the following coastlines, yet only one of the studied regions shows
25 an increase in coastal erosion rates through time – the sites in the eastern Laptev Sea studied by Günther et al. (2013). All other regions show a large amount of spatial variability due to storm climate, the underlying lithology, and local geomorphology.

Our analysis indicates that the length of the sea-ice-free season has increased in all of these locations by varying amounts. Many of the presented sites have rapid rates

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)

of erosion, however, averaging coastal erosion rates over areas with variable geomorphology, lithology, and ice content, may mask the relationship between sea ice change and changing coastal erosion rates. It is also challenging to compare rates measured over different length intervals due to the potential for non-stationarity in erosion rates (e.g. Sadler, 1981). If a signal exists in the relationship between changing sea ice and changing coastal erosion, we are most likely to see it in rapidly eroding regions. It is worth considering what the smallest stretch of coastline for which once can make a significant link between geomorphic rates and changing environment. At Drew Point, most of the coastal erosion rates are made for a 70 km long coastal segment.

We have focused on the relationship between length of open water and coastal erosion. While sea ice provides first order constraints, variability of other changes such as atmospheric warming and storm tracks may play a significant role.

5.2 Drew Point

While we are able to examine the impact of the duration of open water on coastal erosion at well studied sites, it is the passage of storms does the geomorphic work. At Drew Point, we have a rich record of coastal erosion and environmental observations. At this location we can trace the dependence of the processes and rates of coastal evolution first to the nearshore conditions and then determine the dependence of nearshore conditions on sea ice.

Our analysis of coastal exposure at Drew Point can serve as a template for analyzing the impact of changing sea ice on other Arctic coasts. Satellite-derived daily or every-other-day sea ice concentrations are available for the whole Arctic starting in 1979. This dataset documents changes in the length and nature of the open water season, which provides the first order control on Arctic coastal impacts. Yet a full understanding of how changing sea ice will impact coasts depends on both the form and substrate of the coast and the way in which sea ice influences the nearshore conditions in a particular area.

We focus first on the distance to the sea ice edge and then construct a coastal exposure history.

5.2.1 Fetch at Drew Point

At Drew Point, not only has the duration of the open water season increased substantially since the beginning of satellite observations (Overeem et al., 2011), but the distance to the sea ice edge has increased as well. The direction from which wind blows influences whether the water level at the coast is set up or set down (Fig. 4). At Drew Point, erosion is most effective when the water level is set up (Barnhart et al., 2014), and thus it is critical to evaluate the spatial component of changes in the distance to the sea ice edge.

We calculate the distance to the sea ice edge at Drew Point (SIC = 15 %) for all ocean azimuths at 10° increments (see method outlined in Overeem et al., 2011 and applied by Barnhart et al., 2014). Figure 7 illustrates the results from five azimuths: 280, 320, 000, 040, and 080 and shows the increase in the length of the sea-ice-free season, the interannual variability in the length, and the distance to the sea ice edge. The increase in distance to the sea ice edge is particularly pronounced for winds from the west (azimuth 320), the direction from which wind sets up water levels in this region.

These observations motivate asking how the change in fetch is related to the increase in the duration of the sea-ice-free season. We compare the maximum fetch in each azimuth bin for each year with the duration of the sea-ice-free season (Fig. 8). The maximum distance to the sea ice edge has increased through time, more dramatically in the west than in the east (Fig. 8a and b). The evolution of the open water season in this area explains this pattern; open water typically develops from the Bering Strait to the east and from the Canadian Beaufort Sea to the west. By the time it reaches Drew Point, open water extends from Drew Point to the Bering Strait. The length of the sea-ice-free season and the maximum fetch are therefore positively related (Fig. 8c and d), with the largest maximum fetches associated with the longest sea-ice-free seasons. For six of the years, the maximum fetch to the north west (azimuth 320) is large

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



(> 1400 km) with no relationship to the duration of open water conditions (Fig. 8c, orange dots). These are years of extensive open water in the northern Laptev Sea.

5.3 Water exposure history

The increase in open water and fetch provides increased potential for coastal change, but the coast will feel the impact only if a storm passes by. The fetch analysis (Sect. 5.2.1) documents how the open water season has changed at Drew Point, but it does not include nearshore water level and wave conditions. We therefore construct a model of storm surge and waves to reconstruct the water exposure history and test it against observations from Drew Point. The relationship between the wind field and observed changes in the water level and wave height (Fig. 4) suggests that the nearshore water level can be modeled with a simple bathystrophic storm surge model.

We calculate the “directional fetch”, or distance to sea ice edge in the direction from which the wind is blowing (Fig. 9) which serves as a metric for the potential impact of the sea ice retreat on the coast. The directional fetch and the wind field are used as inputs to this model of storm surge and wave height. In this section we first outline the construction of this model (full details are available in the Supplement to Barnhart et al., 2014), apply this model in a theoretical sense to investigate the role of increasing fetch on changes to the nearshore environment, and then calculate the exposure to water level set up and wave field for the period 1979–2012 at Drew Point.

5.3.1 Sea ice control on waves and storm surge

Sea ice reduces the magnitude of waves and storm surge. The details of wave-sea ice interactions is an area of current research and most of this research focuses on propagation of waves into rather than out of the sea ice pack (e.g. Asplin et al., 2012). It is, however, understood that surface waves are attenuated in sea ice (Wadhams et al., 1988; Squire, 2007). Lisitzin (1974) argued that sea ice will reduce the generation of storm surge. Although the wind stress at the atmosphere-ice boundary may be

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



comparable to that at the atmosphere–ocean boundary, the drag coefficient will differ and the wind stress acting on the sea ice will not pile up water to create a storm surge. Observations by Lisitzin (1974) in the Baltic Sea and Henry (1975) in the Beaufort Sea reveal that storm surge amplitudes were smaller when sea ice was present. Other observations are inconclusive (Murty and Polavarapu, 1979).

Storm surge models that incorporate sea ice to some extent have been developed and applied to the Beaufort Sea region. However, like wave-sea ice interactions, fully incorporating sea ice into storm surge modeling is still an area of active research. Kowalik (1984) and Danard et al. (1989) applied a full hydrodynamic model using sea ice observations from Canadian Atmospheric Environment Service Ice Central charts. Two more recent studies are inconclusive about the role of sea ice in storm surge generation, primarily because sea ice is not well incorporated into existing storm surge models (Manson and Solomon, 2007; Lynch et al., 2008). Lintern et al. (2011) used the sea ice edge to set the area over which wind and water could interact in Delft3D model runs and found that changing the distance to the sea ice edge significantly impacted the development of the wave field. We use a similar approach and set the directional fetch as the maximum distance over which wave and set up can generate. Although it does not acknowledge wave generation and propagation through sea ice it produced reasonable results.

5.3.2 Storm surge and wave model

We find that we can successfully model wind-driven set up and wave generation using the storm surge and wave model developed for Drew Point by Barnhart et al. (2014). The model combines the bathystrophic storm surge model of Dean and Dalrymple (1991) and the fetch-limited wave model of Coastal Engineering Research Center (1984). We incorporate sea ice only by using the distance to the sea ice edge as the fetch for storm surge and wave generation, as discussed above. Our treatment of the hydrodynamics is less sophisticated than that of prior researchers, although

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



considering the simple coastal geometry and bathymetry at Drew Point, we think this approach is justified.

This model calculates the water level set up or set down and wave height as a function of the 10 m wind speed, wind direction, fetch, and bathymetry. At each time step, the model determines fetch in a straight line from the sea ice edge to the shore in the direction from which wind is blowing. It then calculates the set up and wave height along the wind path. If the wave height exceeds a critical fraction of the water depth, the model includes the influence of wave set up (see Supplement of Barnhart et al., 2014, for a full explanation of the model).

Fetch is spatially and temporally variable due to the changing wind field, the geometry of the shoreline, and the temporally variable location of the sea ice edge. Based on the geometry of the shoreline near Drew Point, we use a fetch of 1 km for winds blowing offshore (from azimuths ranging from 085 to 200°), limit the fetch to a maximum of 15 km for winds blowing from the direction of the interior of Smith Bay (200 to 260°), and use the distance to the sea ice edge for all other azimuths. These parameters optimize the correlation between observed and predicted water level and wave field characteristics over the summer 2009 field season during which we documented water level.

We recognize that in reality the wind field will not be constant from the sea ice edge to the coastline and that our treatment simplifies the geometry of the storm surge problem. We compare the model with observations collected at Drew Point in 2009 (Fig. 10). Despite all simplifying assumptions, modeled set up and set down agree well with observations made in the summers of 2009 and 2010. It is therefore reasonable to extend the modeled period to 1979–2012 to examine how the wave field and water level have changed over this period, thus evaluating the role of sea ice retreat on coastal hydrodynamics.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract Introduction

Conclusions References

Tables Figures

◀ ▶

◀ ▶

Back Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



5.3.3 Influence of fetch on nearshore conditions

The increasing extent of summertime open water provides increasing fetch. In entirely open water conditions, the maximum directional fetch for any azimuth will be set by the geometry of the Arctic coastline. In these conditions the location, path, and geometry of the storm systems sets limits on the fetch over which set up and waves can form. We ask: what limits on the maximum fetch exist in this system? In the absence of nearshore sea ice, is there a distance that is less than the size of a synoptic scale storm (~ 1000 km) at which set up or wave height “saturate” and no longer continue to increase with increasing fetch?

We use the storm surge and wave model to explore how changing fetch from zero to 1000 km affects the nearshore conditions for wind from all offshore directions and for wind speeds that vary from 1 to 18 ms⁻¹. Figure 11 shows results from three wind directions 280, 000, and 080. This experiment is conducted for a coast with the same geometry as Drew Point in 1 m water depth.

We find that when winds are from the west, increasing fetch and increasing wind speed both result in increased set up and wave heights (Fig. 11, leftmost column). These conditions produce the highest positive set up values. Wind from the north sets water up, but less so than wind from the west (Fig. 11, center column), whereas wind from the east sets water levels down (Fig. 11, right column). We present both the wave heights calculated for water depth dynamically adjusted by the wind driven set up (Fig. 11b) and for wave heights in a constant water depth (Fig. 11c). The wave heights calculated dynamically have directional dependence and can reach higher values due to the increased water depth associated with set up.

In the most realistic model, in which we have dynamic coupling between the set up of water level and waves (Fig. 11b), we do not find a fetch beyond which the set up or wave height “saturate” and no longer continue to increase with increasing fetch. Thus the larger the fetch, the larger the storm surge and wave heights. This contrasts with a non-coupled wave model in which the fetch limited wave model saturates at about

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



100–200 km depending on the water depth and the wind speed (Fig. 11c), and argues for inclusion of this coupling in such models.

5.3.4 Coastal exposure history

We calculate yearly averaged values of environmental conditions and exposure metrics for one offshore pixel at Drew Point for the period 1979–2012 (Fig. 12, cell [208, 226] in the 304×448 Northern Hemisphere grid). The coast is vulnerable when water levels are set up, thus we calculate the number of sea-ice-free days each year and the proportion of these with wind from west to north (azimuths between 270 and 010). Larger fetches can result in larger set up, so we determine the distribution of fetch when wind is from the west. Using our storm surge and wave model output, we calculate three metrics of coastal exposure in the nearshore based on the accumulated (1) “positive set up”, (2) duration of “positive set up”, and (3) wave height over each open water season.

The duration of the sea-ice-free season and the duration of time that wind is from the west show significant positive trends (Fig. 12a). Not only is the duration of time that the wind is from the west increasing, but the mean, 10th, and 90th percentiles of the directional fetch when the wind is from the west and north (the directions that result in water level set up) have increased. We have not fit a trend to Fig. 12b. Figure 12a and b represents a convolution of the changes in fetch shown in Fig. 7 and the wind field.

In Fig. 12c–e we show the yearly and cumulative value for each exposure metric as well as the slope and 95% confidence bounds, R^2 , and RMSE of a linear trend line fit to the yearly values. The positive set has units of meter-day and represents the sum of all the set up that is greater than zero over each summer open water season. The duration of positive set up is the amount of time in each open water season that the set up is positive. The wave height metric is similar to the positive set up in that it represents the sum of all of the wave heights over the open water season.

All three exposure metrics show significant positive trends and significant interannual variability (Fig. 12c–e) which may be due to increases in the magnitude and duration of set up and wave height, or the increased duration of open water conditions. We

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



analyzed each exposure metric normalized by the length of open water for each year and found that the normalized positive set up is the only metric that shows a significant positive trend. Thus, the primary factor that influences these exposure metrics is the length of the open water season.

We calculate one additional measure of the nearshore environment: the distribution of the directional fetch and positive set up (Fig. 13). We find the 5th, 25th, 50th, 75th, and 95th percentile values for each variable (the 95th percentile value represent the value for which 5% of values are above and 95% are below). The distribution of directional fetch (Fig. 13a) and directional fetch at times of positive set up (Fig. 13b) are similar and increase over the observation period (1979–2012). While the mean values of the positive set up (Fig. 12c and f) have not increased over the observation period, the extreme values of positive set up also increase over this time period. The distribution of wave heights over the model time period does not show a trend.

5.3.5 Storm event analysis

Along this stretch of coast, most geomorphic work is done during storm events that set up water. We calculate the number of storms per year, the maximum set up or set down, and wave height for all storms over the 1979–2012 period (defined as continuous time periods with wind speeds of $\geq 10 \text{ m s}^{-1}$ as employed by Atkinson, 2005). We also find the number of “positive set up events” for this time period. For each storm or positive set up event, we extract the highest water level set up or set down and wave height (Fig. 14), and the wind direction and directional fetch at the time of peak wind speed (Fig. 15).

Over the 1979–2012 period we find 799 storms, only 28 of which set water levels up. Over this same time, we find 306 positive set up events. The number of storms per year has not changed through time, and the number of storms that set up water make up a small proportion of the total number of storms (Fig. 14a). This observation mirrors field observations at Drew Point (Wobus et al., 2011; Barnhart et al., 2014)

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



which indicate that small storms can still bring enough set up to lap water at the base of the coastal bluffs and accomplish substantial geomorphic work.

The discrepancy between 28 positive set up storms and 306 positive set up events reveals there are many positive set up events that are not captured in the wind-based definition of a storm though the wind based definition of a storm captures most of the highest values. The number of positive set up events is increasing (95 % confidence bounds on slope: [0.12, 0.62] events per year; $R^2 = 0.25$, RMSE = 6.68). Normalizing by the length of the sea-ice-free season still yields a weak but positive trend (95 % confidence bounds on slope: [0.03, 0.22] events per month of open water per year; $R^2 = 0.16$, RMSE = 0.09). The magnitude of set up events is similar to that of set down events (Fig. 14b) while the wave height during set up events tends to be larger than during set down events (Fig. 14c).

Both storms that set up water and positive set up events have peak wind speeds from the west and north (Fig. 15a). The directional fetch during storms that set down water and for positive set up events has increased through time, whereas the directional fetch during storms that set up water does not exhibit a trend in time (Fig. 15b). High values of extreme positive set up and extreme wave height occur when directional fetch is large which is consistent with our hypothesis that the distance to the sea ice edge controls nearshore conditions through the fetch (Fig. 11).

We can compare this storm analysis to the historical record of storms presented in Lynch et al. (2008) who report observations of historical storms Barrow, AK (five with flooding, eight without over the period 1979–2003). Our analysis is based at Drew Point, which experiences a wind field and storm climate similar to that at Barrow. We find that of the five storms with flooding, we would predict flooding in three of the cases. We correctly predict no flooding for the other eight wind events.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



6 Discussion

In the prior section we present two analyses of the impact of sea ice change on Arctic coasts. Here we discuss the changes in coastal exposure at Drew Point and consider the future of Arctic coasts.

6.1 Changes in coastal exposure at Drew Point

Changes in coastal exposure over the period 1979–2012 are primarily caused by changes in the duration of the sea-ice-free season (Fig. 12a) and the increasing positive extremes of set up magnitude (Fig. 13c). Increasing the sea-ice-free season provides a longer period of time that the nearshore water can interact with the coast, and in the case of Drew Point, results in rapid coastal erosion. The second of these allows for larger waves, and thus more energy to reach the coast.

The distance to the sea ice edge, particularly in the west, has increased. Although the distance to the sea ice edge when the wind blows from the west and north has increased substantially over this time period, we find that increases in the yearly metrics of coastal exposure at Drew Point can be explained most simply by the increased duration of the sea-ice-free season.

Changes in the fetch are not needed to explain the variations in the positive set up, duration of positive set up, or wave height metrics. However, the fetch has changed over the observation period and is reflected in the increasing extreme values of the positive set up (Fig. 13c). It is hard to disentangle set up, fetch, and duration of the sea-ice-free season. A longer sea-ice-free season allows more time for storms to pass over open ocean whereas the directional fetch governs the distance over which storm winds blow, accomplishing either set up or set down. Considering this dependence, it is surprising that we found no trends in the normalized positive set up. However, the number of positive set up events is clearly increasing.

Coastal erosion rates at Drew Point increased from 6.8 myr^{-1} during the period 1955–1979 to 8.7 myr^{-1} during the period 1979–2002 and 13.6 myr^{-1} for the period

TCD

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



2002–2007 (Jones et al., 2009). Overeem et al. (2011) found that the increase in erosion rate over the satellite record tracks the average duration of the open water season. Thus the increase in open water explains most of the change in the coastal erosion rate. However, the increase in size of large set up events (Fig. 13c) and the increase in frequency of positive set up events (Fig. 14a) likely also contribute to the increased erosion rates observed at Drew Point. The water temperature is another factor for controlling erosion rates in ice-rich permafrost coasts, and is influenced by increasing the duration and the area of open water adjacent to the coast (e.g. Barnhart et al., 2014).

6.2 Whole-Arctic coastal change and vulnerability

In the context of a future Arctic in which storminess is predicted to increase, the changes in the duration of open water and fetch distances will likely result in enhanced rates of geomorphic change, inundation, and increased loss of buildings. The geomorphic coastal response to future forcings will depend on both relatively static factors such as the topography, substrate, and geometry of each segment of coast, and dynamic factors including changes in sea ice cover, the number and nature of storms, and the associated nearshore water conditions.

Vulnerability to inundation and salinization is enhanced by low backshore elevations and storm surge sufficient to overtop the beach. Erosion rates are rapid in ice-rich permafrost and depend as well on water temperature. Our analysis of the relationship between ice content, average coastal erosion rate, and length of sea-ice-free season (Fig. 6) and of the previously studied sites with multi-temporal coastal erosion observations (Sect. 5.1.2) however shows that the details of coastal erosion rate are heavily influenced by the local geomorphology and lithology.

As a final step, we consider how the open water season is expanding in six of the Arctic sea sectors (Fig. 16). We plot the distribution of the first and last day of the sea-ice-free season for each Arctic sea sector for 1979 and 2012 along with the average daily insolation, and the average monthly number of storms (from Atkinson, 2005). We do not show the Canadian Arctic (Sector 7) as sea ice persists there throughout the

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



summer season. In most sectors, the sea-ice-free season has expanded more into the fall than into the spring, as Overeem et al. (2011) found in their analysis at Drew Point.

Strong feedbacks are enacted by the expansion of the sea-ice-free season. While the sea-ice-free season in most sectors has roughly doubled in duration since 1979 (the sector averaged factor ranges between 1.5 and 3), it is expanding more into the fall than into the mid-summer (Fig. 16). As the disappearance of the last ice still occurs well after the peak insolation associated with the solstice in mid-June, any expansion earlier into the midsummer exposes the sea surface to increasingly higher insolation. We should therefore expect higher sea surface temperatures, which in turn drives higher erosion rates on ice-rich coastlines. Expansion of the sea-ice-free season into the fall enacts another feedback. As storminess in most sectors increases toward the fall (Fig. 16; Atkinson, 2005), expansion of the sea-ice-free season further into the fall exposes the ocean to winds that can drive higher storm surge and higher waves. This should increase the probability that water levels exceed the base of coastal bluffs, enhancing the rate of erosion.

7 Conclusions

We have presented a pan-Arctic analysis of satellite-based sea ice concentration, an analysis of changing spatial patterns and distance to the sea ice edge at Drew Point, AK, a numerical model that is capable of capturing the nearshore conditions at Drew Point, and an analysis of changing nearshore conditions at Drew Point. This quantifies sea ice control on Arctic coastal processes, and provides an example application to a highly vulnerable coastline.

We calculate three metrics of the nearshore environment, and find that the factor with the most explanatory power is the duration of the open water season. Fetch is increasing at Drew Point, particularly toward the west, increasing the size of large set up events. The total number of storms (as defined by wind speed alone) has not changed, and the number of storms with positive set up is small. However, the number of positive

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



set up events (as defined by water level alone) has increased through time. It is at times when water level is set up that erosion occurs in this area Barnhart et al. (2014).

The duration of sea-ice-free conditions along the entire Arctic coastline has roughly doubled in duration since 1979 and is expanding more into the fall than into the mid-summer. The expanding sea-ice-free season results in different feedbacks in the mid-summer and in the fall. A longer sea-ice-free season in the fall provides open water at a time of greater storminess. This will likely result in increased interaction between the coast and the nearshore water, enhancing the rate of erosion. In addition, expansion of open water into the early summer results in warmer surface water temperatures and higher erosion rates on ice-rich coastlines.

Across the Arctic, at the sites where multi-temporal observations of coastal erosion are available, the relationship between changing sea-ice-free conditions and coastal erosion are complicated by lithology, geomorphology, and ice content.

Changing sea ice cover results in feedbacks that all increase the rates of coastal erosion. Although in detail the vulnerability of a particular reach of coastline will depend on local geomorphology and weather patterns, we should expect coastal erosion rates to rise most dramatically in areas with rapidly expanding sea-ice-free seasons and high ground ice content.

Acknowledgements. The authors thank D. Atkinson for sharing the storm counts reported in Atkinson (2005) and H. Lantuit for sharing the GIS files for the Arctic Coastal Dynamics Database from Lantuit et al. (2012).

This research was funded by ONR-1547946, ONR-1544301, NSF/OPP-1549620 to RSA, IO, and CW. K. R. Barnhart is supported by a NASA Earth and Space Science Fellowship (Award #1549613) and thanks the Alaska Geological Society for their support.

References

ACIA: Impacts of a Warming Arctic: Arctic Climate Impact Assessment, Cambridge University Press, Cambridge, UK, 2004. 2281

TCD

8, 2277–2329, 2014

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Asplin, M. G., Galley, R., Barber, D. G., and Prinsenberg, S.: Fracture of summer perennial sea ice by ocean swell as a result of Arctic storms, *J. Geophys. Res.*, 117, C06025, doi:10.1029/2011JC007221, 2012. 2293

Atkinson, D. E.: Observed storminess patterns and trends in the circum-Arctic coastal regime, *Geo-Mar. Lett.*, 25, 98–109, doi:10.1007/s00367-004-0191-0, 2005. 2281, 2282, 2287, 2298, 2301, 2302, 2303, 2329

Barnhart, K. R., Anderson, R. S., Overeem, I., Wobus, C., Clow, G. D., and Urban, F.: Modeling erosion of ice-rich permafrost bluffs along the Alaskan Beaufort Sea coast, *J. Geophys. Res.-Earth*, 119, doi:10.1002/2013JF002845, 2014. 2279, 2283, 2284, 2285, 2292, 2294, 2295, 2298, 2301, 2303

Bird, E. C. F.: *Coastline Changes, A global review*, Wiley, New York, NY, 1985. 2281

Blunden, J. and Arndt, D. S. (Eds.): *State of the climate in 2011*, *B. Am. Meteorol. Soc.*, 93, S1–S264, 2012. 2281

Brooks, S. M. and Spencer, T.: Temporal and spatial variations in recession rates and sediment release from soft rock cliffs, Suffolk coast, UK, *Geomorphology*, 124, 26–41, 2010. 2282

Brown, J., Jorgenson, M. T., Smith, O. P., and Lee, W.: Long-term rates of coastal erosion and carbon input, Elson Lagoon, Barrow, Alaska, Eighth International Conference on Permafrost, 21–25 July 2003, Zurich, Switzerland, 2003. 2289

Cavalleri, D., Parkinson, P., Gloersen, P., and Zwally, H. J.: *Sea Ice Concentrations from Nimbus-7 SMMR and DMSP SSM/I-SSMIS Passive Microwave Data, 1979–2011*, National Snow and Ice Data Center, 1996. 2284

Clow, G. D., DeGange, A. R., Dirksen, D. V., and Zimmerman, C. E.: Climate change considerations, in: *An Evaluation of the Science Needs to Inform Decisions on Outer Continental Shelf Energy Development in the Chukchi and Beaufort Seas, Alaska*, edited by: Holland-Bartels, L. and Pierce, B., US Geological Survey Circular 1370, 81–108, 2011. 2281

Coastal Engineering Research Center: *Shore Protection Manual*, US Army Engineer Waterways Experiment Station, Coastal Engineering Research Center, 1–652, 1984. 2294

Comiso, J. C.: Warming trends in the Arctic from clear sky satellite observations, *J. Climate*, 16, 3498–3510, 2003. 2281

Danard, M. B., Rasmussen, M. C., Murty, T. S., Henry, R. F., Kowalik, Z., and Venkatesh, S.: Inclusion of ice cover in a storm surge model for the Beaufort Sea, *Nat. Hazards*, 2, 153–171, 1989. 2294

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



- Dean, R. G. and Dalrymple, R. A.: Water Wave Mechanics for Engineers and Scientists, 2 Edn., World Scientific, Singapore, 1991. 2283, 2294
- Eicken, H., Gradinger, R., Gaylord, A., Mahoney, A., Rigor, I., and Melling, H.: Sediment transport by sea ice in the Chukchi and Beaufort Seas: increasing importance due to changing ice conditions?, Deep-Sea Res. Pt. II, 52, 3281–3302, doi:10.1016/j.dsr2.2005.10.006, 2005. 2279
- Greenberg, J., Hart, P., and Grantz, A.: Bathymetric Map of the Continental Shelf, Slope, and Rise of the Beaufort Sea North of Alaska, US Geological Survey Miscellaneous Investigations Series Map 1182-A, 6 p., 1 sheet, scale 1 : 500,000, 1981. 2282
- Günther, F., Overduin, P. P., Sandakov, A. V., Grosse, G., and Grigoriev, M. N.: Short- and long-term thermo-erosion of ice-rich permafrost coasts in the Laptev Sea region, Biogeosciences, 10, 4297–4318, doi:10.5194/bg-10-4297-2013, 2013. 2289, 2290
- Henry, R. F.: Storm Surges, Institute of Ocean Sciences, Victoria, BC, 1–44, 1975. 2294
- Héquette, A., Desrosiers, M., and Barnes, P. W.: Sea ice scouring on the inner shelf of the southeastern Canadian Beaufort Sea, Mar. Geol., 128, 201–219, 1995. 2279
- Hoque, M. A. and Pollard, W. H.: Arctic coastal retreat through block failure, Can. Geotech. J., 46, 1103–1115, 2009. 2283
- IPCC: Climate change 2013: the physical science basis, in: Contribution of Working Group I to the Fifth Assessment Report of the Intergovernmental Panel on Climate Change, Cambridge University Press, 1535 pp., 2013. 2279
- Jones, B. M., Arp, C. D., Jorgenson, M. T., Hinkel, K. M., Schmutz, J. A., and Flint, P. L.: Increase in the rate and uniformity of coastline erosion in Arctic Alaska, Geophys. Res. Lett., 36, L03503, doi:10.1029/2008GL036205, 2009. 2283, 2301
- Jones, E. P.: Circulation in the Arctic Ocean, Polar Res., 20, 139–146, 2001. 2287
- Jorgenson, M. T., Jorgenson, J. C., Macander, M., Payer, D., and E, M. A.: Monitoring of coastal dynamics at Beaufort Lagoon in the Arctic National Wildlife Refuge, Northeast Alaska, Reports on Polar and Marine Research, 413, 22–28, 2002. 2289
- Kobayashi, N.: Formation of thermoerosional niches into frozen bluffs due to storm surges on the Beaufort Sea coast, J. Geophys. Res., 90, 11983–11988, 1985. 2283
- Kobayashi, N., Vidrine, J. C., Nairn, R. B., and Soloman, S. M.: Erosion of frozen cliffs due to storm surge on Beaufort Sea Coast, J. Coastal Res., 15, 332–344, 1999. 2283
- Kovacs, A. and Sodhi, D. S.: Shore ice pile-up and ride-up: field observations, models, theoretical analyses, Cold Reg. Sci. Technol., 2, 210–288, 1980. 2279

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion

- Kowalik, Z.: Storm surges in the Beaufort and Chukchi seas, *J. Geophys. Res.*, 89, 10570–10578, 1984. 2294
- Lantuit, H. and Pollard, W. H.: Fifty years of coastal erosion and retrogressive thaw slump activity on Herschel Island, southern Beaufort Sea, Yukon Territory, Canada, *Geomorphology*, 95, 84–102, 2008. 2289
- Lantuit, H., Overduin, P. P., Couture, N., Wetterich, S., Aré, F., Atkinson, D., Brown, J., Cherkashov, G., Drozdov, D., Forbes, D. L., Graves-Gaylord, A., Grigoriev, M., Hubberten, H. W., Jordan, J., Jorgenson, T., Ødegård, R. S., Ogorodov, S., Pollard, W. H., Rachold, V., Sedenko, S., Solomon, S., Steenhuisen, F., Streletskaia, I., and Vasiliev, A.: The Arctic Coastal Dynamics Database: A New Classification Scheme and Statistics on Arctic Permafrost Coastlines, *Estuar. Coast.*, 35, 383–400, doi:10.1007/s12237-010-9362-6, 2012. 2288, 2289
- Lantuit, H., Overduin, P. P., Couture, N., Wetterich, S., Aré, F., Atkinson, D., Brown, J., Cherkashov, G., Drozdov, D., Forbes, D. L., Graves-Gaylord, A., Grigoriev, M., Hubberten, H. W., Jordan, J., Jorgenson, T., Ødegård, R. S., Ogorodov, S., Pollard, W. H., Rachold, V., Sedenko, S., Solomon, S., Steenhuisen, F., Streletskaia, I., and Vasiliev, A.: The Arctic coastal dynamics database: a new classification scheme and statistics on Arctic permafrost coastlines, *Estuar. Coast.*, 35, 383–400, doi:10.1007/s12237-010-9362-6, 2012. 2281, 2287, 2303, 2317, 2318
- Lantuit, H., Overduin, P. P., and Wetterich, S.: Recent progress regarding permafrost coasts, *Permafrost Periglac.*, 24, 120–130, doi:10.1002/ppp.1777, 2013. 2288
- Lintern, D. G., Macdonald, R. W., Solomon, S. M., and Jakes, H.: Beaufort Sea storm and resuspension modeling. *Journal of Marine Systems*, *J. Marine Syst.*, 127, 14–25, doi:10.1016/j.jmarsys.2011.11.015, 2011. 2281, 2294
- Lisitzin, E.: *Sea-Level Changes*, Elsevier Oceanography Series, 286 pp., New York, 1974. 2293, 2294
- Lynch, A. H., Lestak, L. R., Uotila, P., Cassano, E. N., and Xie, L.: A factorial analysis of storm surge flooding in Barrow, Alaska, *Mon. Weather Rev.*, 136, 898–912, doi:10.1175/2007MWR2121.1, 2008. 2294, 2299
- Manson, G. K. and Solomon, S. M.: Past and future forcing of Beaufort Sea coastal change, *Atmos. Ocean*, 45, 107–122, doi:10.3137/ao.450204, 2007. 2281, 2294

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Mars, J. C. and Houseknecht, D. W.: Quantitative remote sensing study indicates doubling of coastal erosion rate in past 50 yr along a segment of the Arctic coast of Alaska, *Geology*, 35, 583–586, doi:10.1130/G23672A.1, 2009. 2283

Maslanik, J. A., Fowler, C., Stroeve, J., Drobot, S., Zwally, J., Yi, D., and Emery, W.: A younger, thinner Arctic ice cover: increased potential for rapid, extensive sea-ice loss, *Geophys. Res. Lett.*, 34, L24501, doi:10.1029/2007GL032043, 2007. 2281

Maslanik, J., Stroeve, J., Fowler, C., and Emery, W.: Distribution and trends in Arctic sea ice age through spring 2011, *Geophys. Res. Lett.*, 38, L13502, doi:10.1029/2011GL047735, 2011. 2281

Meier, W. N. and Stroeve, J.: Comparison of sea-ice extent and ice-edge location estimates from passive microwave and enhanced-resolution scatterometer data, *Ann. Glaciol.*, 48, 65–70, doi:10.3189/172756408784700743, 2008. 2286

Moore, L. J. and Griggs, G. B.: Long-term cliff retreat and erosion hotspots along the central shores of the Monterey Bay National Marine Sanctuary, *Mar. Geol.*, 181, 265–283, 2002. 2282

Morton, R. A., Miller, T., and Moore, L.: Historical shoreline changes along the US Gulf of Mexico: a summary of recent shoreline comparisons and analyses, *J. Coastal Res.*, 214, 704–709, doi:10.2112/04-0230.1, 2005. 2281

Murty, T. S. and Polavarapu, R. J.: Influence of an ice layer on the propagation of long waves, *Mar. Geodesy.*, 2, 99–125, doi:10.1080/15210607909379342, 1979. 2294

Overeem, I. and Syvitski, J. P.: Shifting discharge peaks in Arctic rivers, 1977–2007, *Geogr. Ann. A*, 92, 285–296, doi:10.1111/j.1468-0459.2010.00395.x, 2010. 2289

Overeem, I., Anderson, R. S., Wobus, C. W., Clow, G. D., Urban, F. E., and Matell, N.: Sea ice loss enhances wave action at the Arctic coast, *Geophys. Res. Lett.*, 38, L17503, doi:10.1029/2011GL048681, 2011. 2281, 2282, 2284, 2286, 2292, 2301, 2302

Rearic, D. M., Barnes, P. W., and Reimnitz, E.: Bulldozing and resuspension of shallow-shelf sediment by ice keels: implications for Arctic sediment transport trajectories, *Mar. Geol.*, 91, 133–147, 1990. 2279

Reimnitz, E., Graves, S. M., and Barnes, P. W.: Beaufort Sea coastal erosion, shoreline evolution, and sediment flux, USGS Open File Report 85-380, 1985. 2283

Reimnitz, E., Graves, S. M., and Barnes, P. W.: Beaufort Sea coastal erosion, sediment flux, shoreline evolution, and the erosional shelf profile, USGS Map 1182-G, 1988. 2283

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



- Ricketts, M.: Hydrographic Survey H07921 of Smith Bay, US Coast and Geodetic Survey, ARW-4251, 1953. 2282
- Sadler, P. M.: Sediment accumulation rates and the completeness of stratigraphic sections, *J. Geol.*, 89, 569–584, 1981. 2291
- 5 Sepp, M. and Jaagus, J.: Changes in the activity and tracks of Arctic cyclones, *Climatic Change*, 105, 577–595, doi:10.1007/s10584-010-9893-7, 2011. 2281
- Serreze, M. C. and Barrett, A. P.: Characteristics of the Beaufort Sea high, *J. Climate*, 24, 159–182, doi:10.1175/2010JCLI3636.1, 2011. 2283
- Serreze, M. C. and Barry, R. G.: *The Arctic Climate System*, Cambridge University Press, New York, 2005. 2287
- 10 Serreze, M. C., Holland, M. M., and Stroeve, J.: Perspectives on the Arctic's shrinking sea-ice cover, *Science*, 315, 1533–1536, doi:10.1126/science.1139426, 2007. 2281
- Sessford, E.: Spatial and temporal analysis of Holocene coastal development: applications to erosion assessment and cultural heritage mitigation in Svalbard, Ph D. thesis, University of Oslo, 2013. 2290
- 15 Solomon, S. M.: Spatial and temporal variability of shoreline change in the Beaufort-Mackenzie region, Northwest Territories, Canada, *Geo-Mar. Lett.*, 25, 127–137, doi:10.1007/s00367-004-0194-x, 2005. 2290
- Squire, V. A.: Of ocean waves and sea-ice revisited, *Cold Reg. Sci. Technol.*, 49, 110–133, doi:10.1016/j.coldregions.2007.04.007, 2007. 2293
- 20 St-Hilaire-Gravel, D., Forbes, D. L., and Bell, T.: Multitemporal analysis of a gravel-dominated coastline in the Central Canadian Arctic Archipelago, *J. Coastal Res.*, 28, 421–441, doi:10.2112/JCOASTRES-D-11-00020.1, 2012. 2290
- Stammerjohn, S., Massom, R., Rind, D., and Martinson, D.: Regions of rapid sea ice change: An inter-hemispheric seasonal comparison, *Geophys. Res. Lett.*, 39, L06501, doi:10.1029/2012GL050874, 2012. 2281
- 25 Urban, F. E. and Clow, G. D.: Air temperature, wind speed, and wind direction in the National Petroleum Reserve–Alaska and the Arctic National Wildlife Refuge, 1998–2011, US Geological Survey Open File Report 2013–1063, 2013. 2283, 2284, 2314
- 30 Urban, F. E. and Clow, G. D.: DOI/GTN-P climate and active-layer data acquired in the National Petroleum Reserve – Alaska and the Arctic National Wildlife Refuge, 1998–2011, US Geological Survey Data Series 812, doi:10.3133/ds812, 2014. 2283

Vasiliev, A., Kanevskiy, M., Cherkashov, G., and Vanshtein, B.: Coastal dynamics at the Barents and Kara Sea key sites, *Geo-Mar. Lett.*, 25, 110–120, doi:10.1007/s00367-004-0192-z, 2005. 2288

5 Wadhams, P., Squire, V. A., Goodman, D. J., Cowan, A. M., and Moore, S. C.: The attenuation rates of ocean waves in the marginal ice zone, *J. Geophys. Res.-Sol. Ea.*, 93, 6799–6818, 1988. 2293

Wobus, C., Anderson, R., Overeem, I., Matell, N., Clow, G., and Urban, F.: Thermal erosion of a permafrost coastline: improving process-based models using time-lapse photography, *Arct. Antarct. Alp. Res.*, 43, 474–484, doi:10.1657/1938-4246-43.3.474, 2011. 2283, 2298

10 Zagórski, P.: Shoreline dynamics of Calypsostranda (NW Wedel Jarlsberg Land, Svalbard) during the last century, *Polish Polar Res.*, 32, 67–99, doi:10.2478/v10183-011-0004-x, 2011. 2290

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version



Interactive Discussion





Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

A. Projected value of the number of open water days per year for 1979



B. Rate of change of the number of sea ice free days (1979-2012)



Title Page

Abstract Introduction

Conclusions References

Tables Figures

◀ ▶

◀ ▶

Back Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Fig. 1. Maps of sea ice change for coastal cells across the whole Arctic. We calculated the number of sea-ice-free days per year – defined as sea ice concentration less than 15% – for the period 1979–2012 for each nearshore cell in which sea ice is shore fast (sea ice present for more than 60 days) for at least 20 years. We fit a linear trend line to number of sea-ice-free days. **(A)** The value of the trend line constraining the projected number of sea-ice-free days in 1979. The inset histogram shows the distribution of the number of sea-ice-free days in 1979 and 2012. **(B)** The resulting rate of change in the number of sea-ice-free days per year (slope of the trend line). Only cells with p values of less than 0.01 are shown. Typical rates on the Beaufort Sea coast of Alaska are $1.5\text{--}2.5\text{ day yr}^{-1}$. Inset histogram shows the distribution of the rate of change. Underlying bathymetry from The GEBCO 08 Grid (version 20100927, <http://gebco.net>).

Sea ice change impacts on Arctic coasts



K. R. Barnhart et al.

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[◀](#)[▶](#)[◀](#)[▶](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

A. Slope of trendline for the first day of continuous open water



B. Slope of trendline for the last day of continuous open water



Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Fig. 2. Trends in the first **(A)** and last **(B)** day of continuous open water across the Arctic. Inset histograms show the distribution of trend line values. Only cells with p values of less than 0.05 are shown. The rate of expansion into the fall is greater than in the spring. There are more days with significant trends in the last day of open water than the first. Note that the color axis has been flipped so that blue represents expanding open water in both panels.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion






Fig. 3. Wind field at Drew Point during both the sea ice (A) and the sea-ice-free season (B). The wind field is dominated by wind from the ENE but show a smaller secondary maximum from the WSW (data from Urban and Clow, 2013).

Sea ice change
impacts on Arctic
coasts

K. R. Barnhart et al.





Fig. 4. Relationship between wind field and nearshore conditions at Drew Point. Winds from the east set water levels down, whereas winds from the west set water levels up (A). As wind speed increases, the magnitude of set up or set down is increased (B). Wave height increases with wind from the east or west (C) and increases with increasing wind speed (D).



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract Introduction

Conclusions References

Tables Figures

◀ ▶

◀ ▶

Back Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Fig. 5. Whole Arctic coastal erosion and deposition (**A**), backshore elevation (**B**), and ground ice content (**C**) from the Arctic Coastal Dynamics Database (Lantuit et al., 2012). 49 % of the segments have erosion rates below 1 myr^{-1} and 40 % of the segments have rates below 2 myr^{-1} . Deposition occurs primarily in deltaic regions, for example the McKenzie delta in the Beaufort Sea. The backshore elevation provides control on the vulnerability of a coast to inundation. Areas with high ice content can experience rapid erosion and are susceptible to changes in the nearshore water temperature.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

[Title Page](#)[Abstract](#)[Introduction](#)[Conclusions](#)[References](#)[Tables](#)[Figures](#)[Back](#)[Close](#)[Full Screen / Esc](#)[Printer-friendly Version](#)[Interactive Discussion](#)




Fig. 6. Comparison of coastal erosion rate and ice content from the Arctic Coastal Dynamics Database (Lantuit et al., 2012) and the the number of sea-ice-free days for 2012 (same analysis as in Fig. 1). For visual clarity, only points with erosion rates greater than 0.1 m yr^{-1} are plotted. Gray tick marks on x and y axes indicate the distribution of values. The relationship between open water days, erosion rate, and ice content is not simple. Up until ~ 220 open water days, the longer the sea-ice-free season, and the higher the ice content, the greater the capacity for high coastal erosion rates.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.




Fig. 7. Distance to the sea ice edge from Drew Point for the period 1979–2012. Both the length of the sea-ice-free season and the distance to the sea ice edge have increased in this time period. The distance to the sea ice edge has increased the most in the northwest direction, which is the direction from which wind blowing sets up nearshore water levels.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change
impacts on Arctic
coasts

K. R. Barnhart et al.





Fig. 8. Maximum distance to the sea ice edge (fetch) as a function of azimuth and time for west (A) and east (B) azimuths and a function of azimuth and duration (C and D). The maximum fetch has increased over the observation period and is typically greater in the west than in the east. The fetch to the west (azimuth 270) reaches a maximum at just under 800 km when it reaches Wrangel Island in the Chukchi Sea. There is a positive relationship between the length of the sea-ice-free season and the maximum fetch (C and D). The maximum fetch to the north west (azimuth 330) has the least well defined relationship with duration of open water conditions (C, light purple dots). This is a direction from which wind sets water levels up at the coast (Fig. 4a).

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.



Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Fig. 9. The “directional fetch” is the distance to the sea ice edge in the direction from which the wind is blowing. The directional fetch is constructed using the hourly wind field from Barrow, adjusted for Drew Point, and the daily location of the sea ice edge. The left panel shows sea ice concentration on 25 August 2008, with distance to the sea ice edge in the direction from which the wind is blowing at that time (red line) and other azimuths (white lines). The directional fetch is used as the maximum distance over which water can be set up or set down and waves can be generated. Based on the wind speed, wind direction, and directional fetch, the set up and set down are calculated (right panel).

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures



Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.




Fig. 10. Measured and modeled set up and wave height for summer 2009. Buoy was deployed in 2.2 m water depth.

Title Page

Abstract Introduction

Conclusions References

Tables Figures

◀ ▶

◀ ▶

Back Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.




Fig. 11. Theoretical set up in 1 m mean water depth **(A)**, wave height calculated in water depth modulated by set up **(B)**, and wave height with a constant water depth at 1 m for an east-west oriented coastal shelf. Wind from the west and the north sets water levels up while wind from the east sets water down. Neither set up or wave height saturate at a critical fetch.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion



Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Environmental Conditions




Fig. 12. Environmental conditions (top row) and exposure metrics (middle row), and normalized exposure metrics (bottom row) calculated at Drew Point over the period 1979–2012. In **(A)** and **(C)–(E)** we show both the value for the yearly metric (left-hand axis) and the cumulative value (right-hand axis). The duration of the open water season and the duration of winds from the west both show a significant increase over this time period **(A)**. The slope of a linear trend line (with 95% confidence bounds in parentheses), the R^2 , and RMSE are given for each yearly metric in the boxes, gray indicates significant at 95% level and white indicates not significant. The distance to the sea ice edge (directional fetch) when the wind is from the west has increased **(B)**. The three exposure metrics – positive set up **(C)**, duration of positive set up **(D)**, and wave height **(E)** – all show large interannual variability and all have significant positive linear trends. Some of the interannual variability in the three exposure metrics is removed if they are normalized by the duration of the open water season **(F–H)**, normalized by magenta line shown in **(A)**. Only the normalized positive set up shows a significant increase **(F)**.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.

Title Page

Abstract

Introduction

Conclusions

References

Tables

Figures

◀

▶

◀

▶

Back

Close

Full Screen / Esc

Printer-friendly Version

Interactive Discussion




Fig. 13. Distribution of directional fetch for each year all open water conditions **(A)**, times when water levels are set up **(B)**, and distribution of modeled positive set up **(C)**. We show the 5th, 25th, 50th, 75th, and 95th percentile values for each variable. The 95th percentile value represent the value for which 5% of values are above and 95% are below. The distribution of directional fetch **(A)** and directional fetch when set up is positive **(B)** are similar and increase over the observation period (1979–2012). While the mean values of the positive set up (Fig. 12c and f) have not increased over the observation period, the extreme values of positive set up also increase over this time period.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.




Fig. 14. Number of storms per year (**A**), magnitude of extreme set up or down (**B**) and magnitude of extreme wave height (**C**) for all storms (defined as wind $\geq 10 \text{ m s}^{-1}$, red dots and gray bars; we also show “positive set up events”, blue dots). Only a small proportion of storms set water up, and the definition of storms based on wind does not capture all positive set up events. There are no clear trends in the number of storms per year, though the number of positive set up events may be increasing.

[Title Page](#)
[Abstract](#)
[Introduction](#)
[Conclusions](#)
[References](#)
[Tables](#)
[Figures](#)
[Back](#)
[Close](#)
[Full Screen / Esc](#)
[Printer-friendly Version](#)
[Interactive Discussion](#)

Sea ice change
impacts on Arctic
coasts

K. R. Barnhart et al.




Fig. 15. Wind direction (A) and directional fetch (B) by year for all storms (defined as wind $\geq 10 \text{ ms}^{-1}$) and for positive set up events. Storms that set up water and positive set up events have winds from the west and north. Directional fetch during storms that set down water and positive set up events has increased through time while directional fetch during storms that set up water does not exhibit this trend.

Sea ice change impacts on Arctic coasts

K. R. Barnhart et al.




Fig. 16. Changes in the length of the open water season from 1979–2012 by sector (panels on left side). Blue shaded (1979) and yellow shaded (2012) regions show the probability density function of the first day of open water (red outline) and the last day of open water (blue outline). The median length of the open water season is shown in the figure background. We show the average daily insolation at 70° north and the average number of storms per month (for the period 1950–2000, from Atkinson, 2005). In many sectors the fall is stormiest; thus expansion of the sea-ice-free season into the fall allows for additional impact by storms. Expansion of the sea-ice-free season into the spring allows for more time at higher insolation levels and thus warmer water temperatures.